



INCORPORATED VILLAGE OF SEA CLIFF
OFFICE OF THE VILLAGE OF SEA CLIFF BUILDING DEPARTMENT
300 Sea Cliff Avenue Sea Cliff, NY 11579 (516) 671-0080

Storm Water Management

1. Management of Storm Water on All Construction Sites:

Storm water must be contained on all construction sites in the Village, regardless of scope or size. Storm water must not wash soil, debris or any substance into the street and into storm drains.

Storm water shall be contained via hay bales or fencing placed to prevent elements on the construction site from washing into the street.

2. Permanent Management of Storm Water on All Completed Projects:

Management of storm water must be built into building plans so that it is retained within the property and does not run onto adjacent properties or the public right of way. No building permit shall be issued without such retention plans.

3. Drywell required

All repair/replacement of new **impermeable** surface driveways or parking areas, as determined by the Building Department, must have a drywell permit.

I understand this notice.

Sign _____

Date _____